BRUHAT BANGALORE MAHANAGARA PALIKE

Item No.89

APPROVED SCHEDULE - B

Tender Notification No: BBMP/ EE /Btp/Ten/02/2012-13 Dated: 15-05-2012 ITEM NO. 75

Name of Work: Estimate for the work of Improvements of roads and Construction of RCC drain in 'A' block, Sahakaranagar in Ward No. 7.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of BR dhananjaya	
				In Figures	In Words
1	228.60	Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods Complete as per Specification and Directions of Engineer in charge of the Work	Cum	60.00	Rupees Sixty Only
2	302.40	Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and slectrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking specification. Complete as per Specification and Directions of Engineer in charge of the Work	Cum	206.00	Rupees Two Hundred Six Only
3	37.80	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms. thick well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per Specification and Directions of Engineer in charge of the Work	Cum	3741.00	Rupees Three Thousand Seven Hundred Forty One Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of BR dhananjaya	
				In Figures	In Words
4	59.85	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses. parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc..,including cost of all materials, labour, HOM of machinery, curing,Complete as per Specification and Directions of Engineer in charge of the Work	Cum	5032.00	Rupees Five Thousand Thirty Two Only
5	47.88	Providing T.M.T steel reinforcement for R.C.C work including straightening cutting, bending, hooking, placing wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of ,materials, labor HOM of machinery Complete as per Specification and Directions of Engineer in charge of the Work	Qtl	6980.00	Rupees Six Thousand Nine Hundred Eighty Only
6	252.00	Providing and laying 10cms thick precast R.C.C. slabs (DATA RATE) Complete as per Specification and Directions of Engineer in charge of the Work	Sqm	1425.00	Rupees One Thousand Four Hundred Twenty Five Only
7	1008.00	Providing and removing centering, shuttering, shuttering, strutting, propping etc.., and removal of form work for vertical surface such as walls at any thickness, including attached plasters, buttresses, plinth and string courses cost of all materials, labour Complete as per Specification and Directions of Engineer in charge of the Work	Sqm	210.15	Rupees Two Hundred Ten and Fifteen Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92